



Tropic Fence, Inc.

"The only fence company you'll ever need"

1864 NW 21st Street, Pompano Beach, FL 33069

Phone 954-978-1250 Fax 954-960-1432

tropicfence@bellsouth.net

PROPOSAL

DATE:04/23/2025

PAGE: 1 OF 2

TO: City of Hallandale Beach Parks, Recreation & Open Spaces Department
501 SE First Ave | Hallandale Beach, FL 33009 |
(954) 457-1452

FOR: DOG PARK
SCAVO PARK.—
900 THREE ISLAND BOULEVARD---
HALLANDALE BEACH, FL 33009
BOB WILLIAMS
RWILLIAMS@HALLANDALEBEACHFL.GOV

CHAIN LINK MATERIAL SPECIFICATIONS

STYLE	CLF		TOTAL HEIGHT	6'		FABRIC HEIGHT	6'	
FABRIC TYPE	BLACK		GAUGE	8		MESH	2"	
SELVAGE	KK		B/W TYPE			TOP RAIL	1 5/8"	
LINE POST	2 ½"	O.D.	SPACED	10'	O.C.	END POST	3"	O.D.
CORNER POST	3"	O.D.	WALK GATE POST	3"	O.D.	DRIVE GATE POST	3"	O.D.
GATE FRAMES: SGL	2"	O.D.	GATE FRAMES: DBL	2"	O.D.	FRAME COATING	BLACK	

CONCRETE FOOTINGS

LINE POSTS	12" X 36"	TERMINAL POSTS	12" X 36"	GATE POSTS	18" X 42"
------------	-----------	----------------	-----------	------------	-----------

MATERIAL LIST

FURNISH AND INSTALL AS PER CONTRACT # 12690-022

REMOVE 1036' OF EXISTING CLF

INSTAL 440' OF 6' HIGH BLAVK VINYL COATED CHAIN LINK FENCE INCLUDING 2EA 12 ' WIDE DOUBLE SWING GATES TOP AND BOTTOM RAIL

INSTALL 600' OF ALUM ASCOTT FENCE PUPPY PICKET 18" INCLUDING 4 <5'WIDE GATES

ITEM 01-01 REMOVAL (1036')
UNIT \$12.00 AMOUNT \$12,432.00

ITEM 01-10 PVC COATED CHAIN LINK FENCE (440')
UNIT \$45.35 AMOUNT \$19,954.00

ITEM 01-29 6'HIGH PVC COATED GATE <5' WIDE (4)
MODIED TO 6' HIGH ASCOTT PUPPY PICKET AS PER R.W. SEE ITEM 3.1.8)
UNIT \$1,285.00 AMOUNT \$5,140.00

ITEM 01-50 - 6' HIGH STEEL PICKET FENCE (600') MODIFIED TO 6' HIGH INDUSTRIAL ASCOTT PUPPY PICKET AS PER R.W. SEE ITEM 3.1.8)
UNIT \$80.00 AMOUNT \$48,000.00

ITEM 01-36 6' HIGH PVC COATED DBL GATE 11'-20' WIDE (2)
UNIT \$2,200.00 AMOUNT \$4,400.00

ITEM 01-61 BOTTOM RAIL (440')
UNIT \$9.00 AMOUNT \$3,960.00

ITEM 3.1.8 - BID ALLOWANCE FOR MATERIALS NOT LISTED
MODIFY FENCE AND GATE TO ALUMINUM ASCOTT WITH PUPPY PICKET
AMOUNT \$6,000.00

ITEM 01-69 FOREMAN LABOR NOT INCLUDED (16HRS)
UNIT \$95.00 AMOUNT 1,520.00

ITEM 01-70 LABORER LABOR NOT INCLUDED (16HRS)
UNIT \$65.00 AMOUNT \$1,040.00

ITEM 01-71 FORMANS HELPER LABOR NOT INCLUDED (16HRS)
UNIT \$80.00 AMOUNT\$1,280.00

TOTAL FOR ALL AMOUNT 103,726.00

Note: Tropic will do 811. City is responsible for any private underground, all clearing, and any permit costs and requirements

NOTES & QUALIFICATIONS; SEE PAGE 2

ADDENDUM __ OF __ SEEN.

DUE TO THE IMPENDING PRICE INCREASES, PRICING CAN BE HELD FOR ONLY 7 DAYS

Tropic Fence, Inc. hereby proposes to furnish all labor, trucks, concrete, equipment and insurance necessary to install the above-described materials as per ground plan herewith. Title to the above property shall remain in the name of Tropic Fence, Inc. until payment in full is received. In the event the money due or any portion has to be collected on demand by an Attorney or by lawsuit, the purchaser agrees to pay all costs of collection including interest at the highest legal rate and a reasonable attorney's fee. This is a retain title contract.

QUOTATION PREPARED BY: LEN SIGAL
TROPIC FENCE, INC GENERAL MANAGER
(954) 978-1250 X106 OFFICE (561) 862-9580 CELL
TROPICLEN@GMAIL.COM

PROPOSAL ACCEPTED:

BY: _____
TITLE: _____
DATE: _____

THANK YOU FOR YOUR BUSINESS!

TROPIC FENCE IS A STATE CERTIFIED MINORITY & BROWARD COUNTY CERTIFIED CBE COMPANY