

## **Change Order Request**

Revisions to the Contract for Construction between **OWNER** and **GENERAL CONTRACTOR** are agreed as follows.

City Of Hallandale Beach	324 SW 2nd Ave, Hallandale Beach	n, FL 33009		
Name		Date of Commencement		
C H A N G E S : Description of the ad	ded/deleted/revised Work			
WORK: Structural Reinforcements a	nd Drywall repairs.			
DEACON FOR CHANCES, Additional		FOR i d do i	Davidsan 7	
REASON FOR CHANGES: Additional	structural reinforcement in concrete columns	as per EOR revised drawing	s-Revision 7.	
LIST OF SUPPLEMENTAL INFORMAT	ION/DRAWINGS (ATTACHED):			
CONTRACT SUM:				
	(including previously approved Change Orders		\$521,784.85	
Contract Sum AFTER this Change:		\$	596,421.44	
TOTAL CHANGE:			\$74,636.59	
CONTRACT DURATION:				
	to this Change (including previously approved	Change Orders):		
Substantial Completion date AFTER	this Change:			
TOTAL CHANGE:		days + or -	0	
APPROVALS:				
CHANGE SUBMITTED BY:				
APPROVED BY:				
a Buttel comme Com	nstruction Group, Inc	02/2	1/2025	
GENERAL CONTRACTOR:	istruction Group, mc	DATE:	1/2025	



## COR #05 - Reinforcement and Drywall repairs Project Name: Historic Village and Curci House Owner: City Of Hallandale Beach Date: 2/21/2025 Project Duration: 247 Days

			Line	e Item	F	Projected		
Description	Qty	Unit	Uni	it Cost	Т	otal Cost	Sub Contractor	Notes
	INT	ERIOR STI	RUCT	URAL RE	INF	ORCEMENT		
1 Reinforcement for new Elevator	1	LS	\$ 3	3,590.00	\$	3,590.00	CCG	Includes reinforcement jacks (2), Installation of jacks and demolition ceiling to access existing wood trusses. Includes reinforcement of wood trusses.
2 Repair ceiling drywall	1	LS	\$	950.00	\$	950.00	CCG	16 SF opening repair. Place drywall and finish to paint. Finish painting by owner.
3 Add new wall diving the two upper bedrooms as directed by Architect	70	SF				2,030.00		Place framing, Insulation and new drywall to divide the two upper rooms as directed and submitted to city by Architect.
ADDITIO	NAL STE	RUCTURA	L CON	ICRETE (	COL	UMNS AND I	BEAMS	
4 Concrete columns and beams	1	LS	\$ 16	6,200.00	\$	16,200.00	O&R	Form,pour and stripping.Layout, Rebar Installation(Drill & Epoxy), Pouring and Finish as per EOR revised drawings.
5 Shoring system supply and installation for existing lintels.	1 1			6,506.00		-	O&R	The engineering calculations,shop drawings and letter of compliance prior slab pours are included.
6 Stucco for new reinforcement columns		LS		4,100.00		4,100.00	Imagine Finishes	
7 Paint for new reinforcement columns	1	LS		2,000.00		2,000.00	AA painting	
8 45 ft Boom lift	1	Month		2,341.38		,	LTC	
9 Remobilization of Florida Lift	1	LS		1,500.00		1,500.00		
10 Securing openings with temporary plywood	1	LS	\$ 1	1,200.00	\$	1,200.00	CCG	
11 Electrical Work	1			2,500.00		2,500.00		off switch.Interior Electrical outlet relocation.
	GE	NERAL R						
12 Project Manager - Onsite - DIRECT COST	100	HR		95.50			CCG	
13 Superintendent - Working Labor Onsite - DIRECT COST	120	HR	\$		\$	7,800.00	CCG	
14 Labor Onsite - DIRECT COST	120	HR	\$		\$	3,060.00	CCG	
15 Final Clean up of first and second floor	1	LS	\$	824.00		824.00	CCG	
16 Concrete washout container	1	EA		750.00		750.00	CCG	
17			SUB	TOTAL:	\$	64,901.38		
18 P&P Bond / Insurance Cost	%	5.0%			\$	3,245.07		
19 Profit	%	10%			\$	6,490.14		
			TO	OTAL:	\$	74,636.59	*Note (see below)	

## \* Notes:

Items to be completed by City Forces/Owner.

Description				
Final painting of new ceiling patch and new diving wall. Drywall to be ready				
for City forces to finish painting.				
Removal and reinstallation of existing windows				
Removal and reinstallation of all windows decorative wood				
Removal and reinstallation of windows treatment/shades				
Removal and reinstallation baseboards				
Removal and reinstallation chair rail on accent wall wood work				
Removal and reinstallation additional paint around windows(interior)				

Exclusions:
Reinforcement of existing windows
Caulking of windows
Any additional stucco and paint around windows
Any interior drywall work /finishes/ paint for windows openings
No addictional reinforcement other than as shown on plans